

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20468-00-00

Spot: SESE Sec/Twnshp/Rge: 23-27S-16W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: WARD Well #: 2-23
County: KIOWA Total Vertical Depth: 4635 feet

Operator License No.: 3959
Op Name: SIROKY OIL MANAGEMENT
Address: PO BOX 464
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4540		WITH 2 SX CMT
CIBP		4609		150.64
PROD	5.5	4625	2030	WITH 200 SX CMT
SURF	8.625	375		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2008 11:00 AM
Plug Co. License No.: 33093 Plug Co. Name: GENESIS WELL SERVICE, INC.
Proposal Rcvd. from: EDGAR SANCHEZ Company: GENESIS WELL SERVICE, INC. Phone: (620) 770-0621

Proposed Plugging Method: SET CIBP @ 4540' & 2 SX CMT OR SAND 50' ABOVE PERFS & 5 SX CMT. PLUG AT 1080' WITH 12 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2008 12:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:
CIBP @ 4540' WITH 2 SX CMT. 1ST PLUG PUMP 20 BBLS FLUID BROKE. CIRCULATION. PUMP 15 SX GEL & 50 SX CMT AT 1080'. 2ND PLUG PULL TO 400' & PUMP 50 SX CMT. 3RD PLUG PULL TO 32' & PUMP 15 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4602	4604		
4590	4596		

INVOICED
DATE 10-17-08
INV. NO. 2009060531

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 22 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY

Plugged through: TBG

District: 01
RECEIVED
SEP 18 2008
KCC Dodge City

Signed Jerry W. Stapleton
PIRATT
(TECHNICIAN)

Form CC-25
PIRATT