

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21684-00-00
Spot: NENESW Sec/Twnshp/Rge: 28-27S-6E
2285 feet from S Section Line, 3297 feet from E Section Line
Lease Name: SIMMONS A Well #: 1
County: BUTLER Total Vertical Depth: 3160 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3153	1320	75 SXS CMT
SURF	8.625	171		80 SXS CMT <u>102.70</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/24/2008 10:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 3010', DUMP BAILED 4 SXS CEMENT ON TOP. CUT 4-1/2" CASING @ 1320', LAYED DOWN 1,070' OF 4-1/2" CASING. W/4-1/2" CASING @ 250', QUALITY WELL SERVICE MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN 4-1/2" CASING. CEMENT CIRCULATED. PLUG DOWN 10:00 AM 7-24-2008. QUALITY WELL SERVICE TICKET #2206.

Perfs:

Top	Bot	Thru	Comments
3066	3068		

INVOICED
DATE 10-16-08
INV. NO. 2009060507

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 18 2008

Remarks: QUALITY WELL SERVICE TICKET #2206

Plugged through: CSG

District: 02

Signed Duane Krueger
(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS

PPT