

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21247-00-01
Spot: NESWNWSE Sec/Twnshp/Rge: 8-34S-3E
1682 feet from S Section Line, 1994 feet from E Section Line
Lease Name: LOVELL C Well #: 1
County: COWLEY Total Vertical Depth: 3382 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3381	1650	190 SX
SURF	8.625	178		150 SX

109.92

Well Type: SWD UIC Docket No: D19400.0 Date/Time to Plug: 08/06/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/06/2008 9:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2210', DUMP BAILED 4 SXS CEMENT ON TOP. CUT 4-1/2" CASING @ 1650', LAYED DOWN 1,300' OF 4-1/2" CASING. W/4-1/2" CASING @ 350', QUALITY WELL SERVICE MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN 4-1/2" CASING. CEMENT CIRCULATED. PLUG DOWN 9:30 AM 8-6-2008. QUALITY WELL SERVICE #2209.

Perfs:

Top	Bot	Thru	Comments
2264	2280		
INVOICED			
DATE <u>10-16-08</u>			
INV. NO. <u>2009060507</u>			
RECEIVED			
KANSAS CORPORATION COMMISSION			
SEP 18 2008			

Remarks: QUALITY WELL SERVICE TICKET #2209. DOCKET #D13,400

Plugged through: CSG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS

PK