

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21806-00-00
Spot: N2SESE Sec/Twnshp/Rge: 8-34S-3E
896 feet from S Section Line, 663 feet from E Section Line
Lease Name: LOVELL C Well #: 2
County: COWLEY Total Vertical Depth: 2577 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2559	1830	75 SX
SURF	8.625	265		225 SX

83.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/04/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/04/2008 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2500', DUMP BAILED 4 SXS CEMENT ON TOP. CUT 4-1/2" CASING @ 1830', LAYED DOWN 1,480' OF 4-1/2" CASING. W/4-1/2" CASING @ 350', QUALITY WELL SERVICE MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN 4-1/2" CASING. CEMENT CIRCULATED. PLUG DOWN 3:30 PM 8-4-2008. QUALITY WELL SERVICE TICKET #2208.

Perfs:

Top	Bot	Thru	Comments
2559	2577		

INVOICED
DATE 10-16-08
INV. NO. 2009060507

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 18 2008

Remarks: QUALITY WELL SERVICE TICKET #2208.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 02

Signed *Duane Krueger*
(TECHNICIAN)

PKG