

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22151-00-00
Spot: NWSENE Sec/Twnshp/Rge: 32-25S-3E
1650 feet from N Section Line, 990 feet from E Section Line
Lease Name: REED Well #: 4
County: BUTLER Total Vertical Depth: 2858 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2857	2200	75 SX
SURF	8.625	213		150 SX

92.89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 07/17/2008 9:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2695', DUMP BAILED 5 SXS CEMENT ON TOP. CUT PIPE @ 2200', LAYED DOWN (2200') 4 1/2" CASING, RIH W/TBG @ 265', QUALITY WELL SERVICE MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 09:30 AM. 7/17/2008. QUALITY WELL SERVICE CEMENT TICKET #2203.

Perfs:

Top	Bot	Thru	Comments
2747	2750		

INVOICED
DATE 10-16-08
INV. NO. 2009060514

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 12 2008


Remarks: QUALITY WELL SERVICE CEMENT TICKET #2203

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

