

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25808-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 13-12S-19W  
1090 feet from N Section Line, 1550 feet from E Section Line  
Lease Name: JOY Well #: 1  
County: ELLIS Total Vertical Depth: 3900 feet

Operator License No.: 32948  
Op Name: TOMLINSON OPERATING, LLC  
Address: 7154 W. STATE ST #302  
BOISIE, ID 83714

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	330		

126.75

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2008 2:00 PM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: BILL OHMAN Company: TOMLINSON OPERATING, LLC Phone: (208) 229-1937

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE  
Date/Time Plugging Completed: 09/11/2008 4:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3833' w/25 sxs.  
2nd. Plug at 1510' w/25 sxs.  
3rd. Plug at 860' w/100 sxs.  
4th. Plug at 380' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 25 sxs.

Perfs:

INVOICED  
DATE 10-16-08  
INV. NO. 2009060515

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 17 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

