

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20293-00-04

Spot: SENESE

Sec/Twnshp/Rge: 31-29S-5E

1768 feet from S Section Line, 370 feet from E Section Line

Lease Name: HOLT

Well #: 4

County: BUTLER

Total Vertical Depth: 2817 feet

Operator License No.: 30169

Op Name: DOUBLE "D" OIL COMPANY, INC.

Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	2151		
PROD	5.5	2816		80 SX
SURF	8.625	208		150 SX
T1	2.875	1860		

91.55

Well Type: SWD

UIC Docket No: D28192.0

Date/Time to Plug: 09/18/2008 8:00 AM

Plug Co. License No.: 5495

Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING

Proposal Rcvd. from: DON BUTLER

Company: DOUBLE D OIL COMPANY INC

Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 09/18/2008 8:45 AM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 1750', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 5-1/2" CASING @ 300', LAYED DOWN CASING. RIH W/TBG @ 280', CONSOLIDATED MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8:45 A.M. 9-18-2008. CONSOLIDATED CEMENT TICKET #19067.

Perfs:

Top	Bot	Thru	Comments
1966	1967		
1820	1821		

INVOICED

DATE 10-20-08

INV. NO. 2009060538

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 26 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #19067.

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

PKP