

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20355-00-00
Spot: NENESE Sec/Twnshp/Rge: 31-29S-5E
2347 feet from S Section Line, 434 feet from E Section Line
Lease Name: ROCK NORTHEAST UNIT Well #: 6
County: BUTLER Total Vertical Depth: 2760 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2760	1160	50 SX
SURF	8.62	211		150 SX CMT <u>89.70</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2008 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DON BUTLER Company: DOUBLE D OIL COMPANY INC Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/18/2008 11:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2655', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 5-1/2" CASING @ 1160', LAYED DOWN CASING. RIH W/TBG @ 280', CONSOLIDATED MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11:30 A.M. 9-18-2008. CONSOLIDATED CEMENT TICKET #19069.

Perfs:

Top	Bot	Thru	Comments
2718	2719		

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #19069.

Plugged through: TBG

INVOICED
DATE 10-20-08
INV. NO. 2009060538

District: 02

Signed Duane Krueger
(TECHNICIAN)