

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20559-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 32-29S-5E
1611 feet from S Section Line, 5004 feet from E Section Line
Lease Name: ROCK UNIT NORTHEAST Well #: 3
County: BUTLER Total Vertical Depth: 2830 feet

Operator License No.: 30169
DOUBLE D OIL COMPANY INC String Size Depth (ft) Pulled (ft) Comment
Op Name: STELBAR OIL CORPORATION, INC. PROD 5.5 2829 675 80 SX
Address: 1625 N WATERFRONT PKWY 2009 Jean et SURF 8.625 205 135 SXS CMT 91.98
Winfield, WICHITA, KS 67206 K 56715 KCC PRT PEN T-1

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/18/2008 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DON BUTLER Company: DOUBLE D OIL COMPANY Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/18/2008 10:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2720', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 5-1/2" CASING @ 675', LAYED DOWN CASING. RIH W/TBG @ 280', CONSOLIDATED MIXED & PUMPED 105 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10:00 A.M. 9-18-2008. CONSOLIDATED CEMENT TICKET #19068.

Perfs:

Top	Bot	Thru	Comments
2792	2797		

INVOICED
DATE 10-20-08
INV. NO. 2009060538

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #19068.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)