

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCC Agent
per spot
research*
API Well Number: 15-191-21513-00-00
Spot: S2SENE
sesw scene

Sec/Twnshp/Rge: 10-30S-1E
2925 feet from S Section Line, 782 feet from E Section Line
Lease Name: COWSKIN CREEK UNIT C Well #: 1
County: SUMNER Total Vertical Depth: 3480 feet

Operator License No.: 30729
Op Name: GABEL, CRAIG
Address: 2131 S BROADWAY
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3479	2065	125 SX
SURF	8.625	210		175 SX

113.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2008 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK 50' ABOVE THE PERFS AND CAP WITH 4 SKS OF CMT. RECOVER CASING, CIRC. CMT FROM 260' TO 0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/17/2008 12:45 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3200', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED 2065' AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 300', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3308	3312		
3294	3301		

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10/20/08
INV. NO. 2009060539

Remarks: COPELAND ACID SERVICE. 60/40 4% GEL 125 SKS

Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)