

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-20201-00-01  
Spot: SWNENW Sec/Twnshp/Rge: 2-34S-2E  
4290 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: CASTER UNIT Well #: 2-4  
County: SUMNER Total Vertical Depth: 2804 feet

Operator License No.: 32984  
Op Name: GOBY ENERGY, INC.  
Address: 51000 TWO RIVERS PLAZA  
GLENWOOD SPRINGS, CO 81601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2803		150 SX
SURF	8.625	249		250 SX

91-13

Well Type: SWD UIC Docket No: E15716.3 Date/Time to Plug: 08/07/2008 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (785) 623-1174

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/07/2008 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2680', DUMP BAILED 4 SXS CEMENT ON TOP. TESTED CASING @ 100#, HELD OK. PERFORATED SQUEEZE HOLES @ 302', RIH W/TBG @ 310', QUALITY WELL SERVICE MIXED & PUMPED 175 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TBG & SWEDGED TO 4-1/2" CASING AND SQUEEZED CEMENT AROUND. CEMENT CIRCULATED. PLUG DOWN 8-7-2008, 4:00 P.M. QUALITY CEMENT TICKET #2211.

Perfs:

Top	Bot	Thru	Comments
2724	2732		

INVOICED

DATE 10-20-08  
INV. NO. 2009060540

RECEIVED  
KANSAS CORPORATION COMMISSION  
**SEP 26 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: E-15,716  
Plugged through: TBG

District: 02

Signed *Duane Krueger*  
(TECHNICIAN)

*PKT*