

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-10396-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 23-32S-2E  
4132 feet from S Section Line, 4081 feet from E Section Line  
Lease Name: Wenkich B KCCPKT Well #: 19  
County: SUMNER Total Vertical Depth: 2035 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2007		100 SX
SURF	8.625	210		125 SX

*66.14*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/21/2008 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 1950', AND CAPPED WITH 5 SKS CMT. REC PIPE. CMT FROM 260'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/21/2008 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 1950', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 1150' AND PULLED FROM THE WELLBORE. CASING WAS RUN BACK TO 260' AND CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2007	2035		

**INVOICED**  
DATE 10-20-08  
INV. NO. 2009060543


RECEIVED  
KANSAS CORPORATION COMMISSION  
**SEP 26 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUAILTY OIL WELL CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

