

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-00844-00-00  
Spot: SENW Sec/Twnshp/Rge: 16-31S-8W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: CRITSER A Well #: 1-16 *KCC Plot*  
County: HARPER Total Vertical Depth: 4534 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4542	2430	100 SX
SURF	8.625	196		150 SX

147.36

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2008 9:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE THE PERFS CAP WITH 5 SKS OF CMT. RECOVER CASING, 35 SKS 1400', 35 SKS 950', CIRC. CMT FROM 250'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/11/2008 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4050' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2430' AND PULLED TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 250', WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4405	4409		
4401	4405		
4198	4204		
4102	4108		

**INVOICED**

DATE 10/20/08  
INV. NO. 2009060544

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 26 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING 60/40 4% GEL #2222

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)