

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20182-00-01

Spot: NWNE

Sec/Twnshp/Rge: 10-34S-8W

KCCPKT 4620 feet from S Section Line, 1980 feet from E Section Line

Lease Name: RITTER B OWWO

Well #: 1-10

County: HARPER

Total Vertical Depth: 4700 feet

Operator License No.: 5003

Op Name: MCCOY PETROLEUM CORPORATION

Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4698	3420	150 SX
SURF	8.625	265		225 SX

15275

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 09/03/2008 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE

Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK T 4010 AND 4 SKS CMT. RECOVER CASING, 35 SKS 1400, 35 SKS 900, CIRC 315-0

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: NONE

Date/Time Plugging Completed: 09/03/2008 10:30 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND FROM TD TO 4408', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 3420', AND PULLED TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 310', WHERE CMT WAS CURCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4630	4640		
4459	4464		

INVOICED
DATE 10-20-08
INV. NO. 2009060544


RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING CO 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

