

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21279-00-00
Spot: S2S2S2 Sec/Twnshp/Rge: 14-33S-6W
255 feet from S Section Line, 2687 feet from E Section Line
Lease Name: FLINN Well #: 1
County: HARPER Total Vertical Depth: 4470 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4469		100 SX
SURF	8.625	214		140 SX

145.28

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PERFS 4391-99, PBTD 4414, SAND BACK TO 4330 AND 4 SKS OF CMT, NO CASING RECOVERY, CASING BACK SIDE SQUEEZED FROM 300'-0'. PERF AT 1000' PUMP 35 SKS OF CMT. PERF AT 700', PUMP 35 SKS OF CMT. CIRC CMT INSIDE CASING FROM 270'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/04/2008 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED BACK FROM TD TO 4330', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS PERFD AT 100', AND 700'. TUBING WAS RUN TO 1000', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 270', WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4391	4399		

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 26 2008

CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10-20-08
INV. NO. 20090605416

Remarks: QUALITY OIL WELL CEMENTING 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)