

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22432-00-00
Spot: NENESW Sec/Twnshp/Rge: 24-31S-1W
2253 feet from S Section Line, 3074 feet from E Section Line
Lease Name: ZEKA Well #: 1-24
County: SUMNER Total Vertical Depth: 3740 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	64		80sx
PROD	4.5	3741	2660	100/25sx
SURF	8.625	453		275sx
T1	2.375	3731		

12155

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2008 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3580' AND 4 SKS OF CMT. RECOVER CASING, PULL CASING TO 500', SPOT 35 SKS OF CMT. PULL CASING TO 250', CIRC CMT TO SURFACE

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 08/20/2008 9:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3580', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2660', AND PULLED TO 500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 250', WHERE CMT WAS CIRCD TO SURFACE. PULLED REMAINING CASING AND TOPPED OFF CMT.

Perfs:

Top	Bot	Thru	Comments
3640	3648		

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10-20-08
INV. NO. 2009060544

Remarks: UNITED CMTG #2215 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

[Handwritten mark]