

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 23 Twp. 10S Rge. (E) 24 (W)

Location as "NE/CNW&SW&" or footage from lines 155' NE of SW SW NW

Lease Owner Martin Explorations

Lease Name Billings Well No. 1

Office Address 527 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 24 19 70

Application for plugging filed August 25 19 70

Application for plugging approved 19


Plugging commenced August 24 19 70

Plugging completed same 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4015 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas
08-31-70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 1100', plug and 70 sacks cement thru-drill pipe with pump truck;
Plug at 215' and 20 sacks cement;
Mud to 40', 1/2 sack hulls and 10 sacks cement.
Cemented rat hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1970
CONSERVATION DIVISION
Wichita, Kansas
08-27-70

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aspen Drilling Co.
Address P. O. Box 783, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
William S. Schachle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William S. Schachle
William S. Schachle, Great Bend, Kansas
(Address)

Sworn to before me this 25th day of April August, 1970

April 18, 1972

Theora Holleman
Theora Holleman Notary Public.



DRILLERS LOG

COMPANY: Martin Explorations
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Billings #1
 LOCATION: 155' NE of SW SW NW
 Section 23-T10S-R24W
 Graham County, Kansas
 ELEVATION: 2428' K. B.
 SURFACE CASING: 5 jts. (202') 8 5/8"
 COMMENCED: August 17, 1970
 COMPLETED: August 24, 1970
 ROTARY TOTAL DEPTH: 4015'

<u>FORMATION</u>	<u>DEPTH</u>
Shale & Shells	1250
Shale Iron Sand	1800
Shale	2265
Shale & Lime	2475
Lime	2575
Shale & Lime	2737
Lime & Shale	3462
Shale & Lime	3560
Lime	4015
RTD	4015

Ran 5 jts. (202') 8 5/8" casing set at 209' with 150 sacks cement. Cement did circulate.
 DST #1 3794-3825
 DST #2 3920-3935
 Ran electric log.
 D & A

RECEIVED
 STATE CORPORATE COMMISSION
 AUG 27 1970
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle, Affiant

Subscribed and sworn to before me this 25th day of August, 1970.

Theora Holleman
 Theora Holleman, Notary Public

My commission expires: April 18, 1972