

LEASE NAME Cochran

WELL NUMBER 1

1,650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 26 TWP. 10 RGE. 24 (E) or (W)

COUNTY Graham

Date Well Completed 10-24-97

Plugging Commenced 10-24-97

Plugging Completed 10-24-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, KS. 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 10-24-97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,935'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	217'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Push bridge plug to 2,000', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 1,125', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 275', pump 40 sax cement on plug thru drill pipe. Push plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement in rathole and 10 sax cement in mousehole.

Name of Plugging Contractor Shields Oil Producers, Inc. License No. \_\_\_\_\_

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Operator) or (OPERATOR)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg.  
 PO Box 709, Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 4th day of November, 19 97

Herb Phillips  
 Notary Public

My Commission Expires:

