

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 28 TWP. 10S RGE. 24W E/W
Location as in quarters or footage from lines:
C. SE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Don E. Pratt
Lease Name McCall 1-28 Well No. 1-28 ^{AUG} ₂₀₀
Office Address P.O. Box 370 Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 12-8-81
Plugging completed 12-28-81
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ bottom _____ T.D. 4010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	172'	none
				5-1/2"	4009'	1705'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

~~Plugged off bottom with sand to 3950' and set 5 sacks cement. Shot casing @2812' and
1702'. Pulled a total of 48 joints of pipe. Plugged well with 4 sacks hulls, 15
sacks gel, 1 sack hulls, 70 sacks cement, 10 sacks gel, plug, 70 sacks cement.
Plugging Completed.~~

RECEIVED
STATE CORPORATION COMMISSION
12-31-81
DEC 31 1981
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 81

My Commission expires:




Irene Hoover
Notary Public.

API 15-065-20,968 WELL LOG
-00-00

COMPANY Don E. Pratt
 FARM McCALL NO. 1-28
 RIG. NO. 15
 TOTAL DEPTH 4010'
 COMM. 10/27/77 COMP. 11/4/77
 CONTRACTOR Murfin Drilling

SEC. 28 T. 10s R. 24w
 LOC. C SE/4

COUNTY Graham, Ks
 KANSAS



CASING
 20 10
 15 8 5/8" @ 172' w/140 sx
 12 6
 13 5 1/2" @ 4009' w/200 sx

ELEVATION
 PRODUCTION Producer

FIGURES INDICATE BOTTOM OF FORMATIONS

surf soil & sand	80
clay	120
shale, blue shale	172
cement, shale	190
shale, sand	1135
shale	1544
sand	1760
red bed	1983
shale	2685
shale, lime	3525
lime	4010
RTD	4010

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 23 1977
 CONSERVATION DIVISION
 Wichita Kansas

State of Kansas
 County of Sedgwick ss:

I, Wm. S. Shropshire of the Murfin Drilling Company

do hereby state that the above and foregoing is a true and correct copy of the log of the McCall #1-28 well.

Subscribed and sworn to before me this 28th day of November 19 77

Wm. S. Shropshire

My Commission Expires: My Comm. Exp. March 13, 1979

JOLENE S. FRIEDMAN, STATE NOTARY PUBLIC

Jolene S. Friedman
 NOTARY PUBLIC