

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 28 TWP. 10S RGE. 24W E/W  
Location as in quarters or footage from lines:

SW SW SW


Lease Owner Don E. Pratt

Lease Name McCall 2-28 Well No. 2-28 *HWB lcc*

Office Address P.O. Box 370 Hays, Kansas 67601

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 12-11-81

Plugging completed 12-28-81

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	128'	none
				4-1/2"	3998'	3042'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed bottom plug to 3700', ran 50' of sand and set 4 sacks cement. Shot casing @3041' and pulled a total of 74 joints of pipe. Plugged well with 4 sacks hulls, 15 sacks gel, 1 sack hulls, 70 sacks cement, 10 sacks gel, plug, 70 sacks cement. Plugging Completed.

RECEIVED  
STATE CORPORATION COMMISSION  
12-31-81  
DEC 31 1981  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 81

My Commission expires 

Irene Hoover  
Notary Public.

API # 15,065-21,124-00-00  
WELL LOG


COPY FOR YOUR INFORMATION

COMPANY Don Pratt  
FARM McCALL NO. 2-28

SEC. 28 T. 10S R.24W  
LOC. SW SW SW

RID. NO. 16  
TOTAL DEPTH 4000'  
COMM. 5-16-79 COMP. 5-24-79

COUNTY Graham,  
KANSAS



CONTRACTOR Murfin Drilling Company

CASING  
20 10  
15 8 -5/8" w/90 sx.  
12 6  
13 5  
4 1/2" w/175 sx.

ELEVATION  
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

35'	Sand
129'	Shale
725'	Sand & Shale
985'	Clay & Shale
1030'	Pyrite & Sand stringers
1540'	Sand & Clay & Shale
1993'	Sand & Shale
2027'	ANHYDRITE
2250'	Sand & Shale
2525'	Sand (Red Bed) Shale
2725'	Shale
2870'	Shale & Lime
3000'	Shale
3415'	Shale & Lime
3560'	Shale
3768'	Shale & Lime
3855'	Lime & Shale
3925'	Shale & Lime
3960'	Lime & Shale
4000'	Lime RTD

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 23 1981  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Sedgwick

I, Wm. S. Shropshire, Asst. Gen. Mgr. of the Murfin Drilling Company Company

upon oath state that the above and foregoing is a true and correct copy of the log of the McCALL #2-28 well.

*Wm. S. Shropshire*  
Wm. S. Shropshire, Asst. Gen. Mgr.

Subscribed and sworn to before me this 3rd day of June 1979

My Commission Expires: May 21, 1983

*Linda Lynch*  
Linda Lynch - NOTARY PUBLIC

