

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21477 ^{00 00}
LEASE NAME OTT Wichita, KS 67202

TYPE OR PRINT **RECEIVED** NUMBER 1

APR 14 2003

NOTICE: Fill out completely 4290 Ft. from S Section Line
and return to Cons. Div. 330 Ft. from E Section Line
office within 30 days

LEASE OPERATOR KCC WICHITA SEC 34 TWP. 10S RGE. 24W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY GRAHAM
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/4/03

Character of Well I OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 4/4/03
Plugging Completed 4/4/03

The plugging proposal was approved on 4/4/03 (date)
by Herb Deines w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no
Producing Formation LKC Depth to Top 3826 Bottom 3919 TD 4325 Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	287	8 5/8	287	0
		Prod	4293	4 1/2	4293	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Perf 4 1/2" csg @ 2065 & 1200. Tied onto 4 1/2" csg. Pumped 210 sxs 60/40 poz 10% gel 400# hulls. Max Press 600#. ISIP 500#. Tied onto 8 5/8" Pumped 90 sxs 100# hulls Max. press 500# ISIP 300#. Well P/A. Witnessed and approved by Herb Deines w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 7th day of April, 2003

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



15-065-21477-00-00

ALLIED CEMENTING CO., INC.

P.O. BOX 31
RUSSELL, KS 67665
PH (785) 483-3887
FAX (785) 483-5566
FEDERAL TAX ID# 48-0727860

*
* I N V O I C E *
*

Invoice Number: 089639

Invoice Date: 04/08/03

Sold Murfin Drilling Co.
To: 250 N. Water, St. #300
Wichita, KS
67202

Cust I.D.....: Murfin
P.O. Number...: Ott #1
P.O. Date.....: 04/08/03

Due Date.: 05/08/03
Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	180.00	SKS	7.1500	1287.00	T
Pozmix	120.00	SKS	3.8000	456.00	T
Gel	21.00	SKS	10.0000	210.00	T
Hulls	5.00	SKS	18.0000	90.00	T
Handling	300.00	SKS	1.1500	345.00	T
Mileage (50)	50.00	MILE	15.0000	750.00	T
300 sks @\$.05 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp trk	50.00	MILE	3.5000	175.00	T

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$ 378.80
ONLY if paid within 30 days from Invoice Date

Subtotal:	3788.00
Tax.....:	257.58
Payments:	0.00
Total...:	4045.58

RECEIVED
APR 14 2003
KCC WICHITA

ALLIED CEMENTING CO., INC. 13406

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>4-11-63</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>8:30 AM</u>	JOB START	JOB FINISH <u>9:30 AM</u>
LEASE <u>OH</u>	WELL # <u>1</u>	LOCATION <u>Wekaeny 2 N Coline 6 W 45</u>			COUNTY <u>Graham</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR _____ OWNER _____

TYPE OF JOB Plug

HOLE SIZE _____	T.D. _____
CASING SIZE _____	DEPTH _____
TUBING SIZE _____	DEPTH _____
DRILL PIPE _____	DEPTH _____
TOOL _____	DEPTH _____
PRES. MAX _____	MINIMUM _____
MEAS. LINE _____	SHOE JOINT _____
CEMENT LEFT IN CSG. _____	
PERFS. _____	
DISPLACEMENT _____	

CEMENT

AMOUNT ORDERED

300# 60/40-10

500 # HULLS

COMMON	<u>180</u>	@	<u>7.15</u>	<u>1287.00</u>
POZMIX	<u>120</u>	@	<u>3.80</u>	<u>456.00</u>
GEL	<u>21</u>	@	<u>10.00</u>	<u>210.00</u>
CHLORIDE		@		
<u>Hulls</u>	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>300</u>	@	<u>.45</u>	<u>345.00</u>
MILEAGE	<u>5 1/2</u>	@	<u>14.00/mile</u>	<u>750.00</u>
TOTAL				<u>3138.00</u>

EQUIPMENT

PUMP TRUCK # _____	CEMENTER <u>Bill</u>
	HELPER <u>PAC</u>
BULK TRUCK # _____	DRIVER <u>Shane</u>
BULK TRUCK # _____	DRIVER _____

REMARKS:

pump down 4 1/2 w/ 210 lbs
w/ 400 # Hulls max 600 #
Shot in 500 # Shot In
pump down 100 w/ 90 lbs cement
w/ 100 # Hulls max 500 # 300 # Shot In

SERVICE

DEPTH OF JOB _____	
PUMP TRUCK CHARGE _____	<u>475.00</u>
EXTRA FOOTAGE _____	@ _____
MILEAGE <u>50</u>	@ <u>3.50</u> <u>175.00</u>
PLUG _____	@ _____
	@ _____
	@ _____
TOTAL <u>650.00</u>	

CHARGE TO: AUFIN

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE John Lusk

PRINTED NAME _____