

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21795-00-00
Spot: NWNW Sec/Twnshp/Rge: 17-35S-43W
660 feet from N Section Line, 660 feet from W Section Line
Lease Name: GRASSLAND Well #: 1-17
County: MORTON Total Vertical Depth: 4420 feet

Operator License No.: 31722
Op Name: GLACIER PETROLEUM COMPANY, OK
Address: 9400 N BROADWAY EXT STE 610
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2825		WITH 2 SX CMT
CIBP		4151		
COND 20		41		6 YDS. 143.65
PROD 4.5		4414	0	WITH 225 SX CMT
SURF 8.625		1446		WITH 700 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/19/2008 8:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: DAVID REMPert Company: GLACIER PETROLEUM Phone: (440) 584-0262

Proposed Plugging Method: SET CIBP @ 2825' WITH 2 SX CMT. PERFORATE @ 1480' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 09/19/2008 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 2825' WITH 2 SX CMT. PERFORATE 4 1/2" @ 1480'. CIRCULATED 250 SX CMT TO SURFACE. TIED ONTO BACKSIDE & PUMPED 18 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4284	4294		MORROW
2940	2941		
2930	2931		
2878	2888		TOPEKA

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

DATE 10-27-08
INV. NO. 2009060014

Plugged through: CSG

District: 01

RECEIVED
OCT - 6 2008
KCC Dodge City

Signed Eric MacLaren
(TECHNICIAN)