

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-00855-00-00  
Spot: NENESW Sec/Twnshp/Rge: 1-31S-9W  
2283 feet from S Section Line, 3017 feet from E Section Line  
Lease Name: WINGATE Well #: 1  
County: HARPER Total Vertical Depth: 4460 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4460	2050	100 SX
SURF	8.625	405		0

144.95

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2008 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND PERFS TO 4360 AND CAP WITH 5 SKS CMT. RECOVER CASING. SPOT 35 SKS AT 1400', SPOT 35 SKS 950', SPOT 35 SKS AT 500', CIRC CMT FROM 250'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/02/2008 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED TO 4360' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2050', AND PULLED TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 250', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4414	4430		

INVOICED

DATE 10-27-08  
INV. NO. 2009060618

RECEIVED  
KANSAS CORPORATION COMMISSION  
**OCT 09 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING. 60/40 POZ 4% GEL #2379

Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

[Handwritten mark]