

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21733-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 35-30S-9W
1930 feet from S Section Line, 330 feet from W Section Line
Lease Name: LEE Well #: 3
County: KINGMAN Total Vertical Depth: 4458 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4457	1840	125 SXS CMT
SURF	8.625	220		165 SXS CMT

144.89

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/30/2008 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK THE PERFS TO 4360 AND CAP WITH 4 SXS OF CMT. RECOVER CASING. SPOT 35 SKS AT 1500', 35 SKS AT 900', CIRC CMT FROM 270-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/30/2008 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4358' AND CAPPED WITH 4 SKS OF CMT. THE SAND LINE PARTED, LEAVING THE CASING KNIFE IN THE HOLE AT 3010', TRIED TO RECOVER KNIFE WITH SPEAR BUT COULD NOT RETRIEVE. GAS BLEW FROM HOLE AT 3010, WHEN KNIFE WAS MOVED FROM THE SLOT IN THE COLLAR. LEFT KNIFE IN PIPE. WENT IN CASING WITH A NEW KNIFE AND RECOVERED CASING FROM 1840'. PULLED CASING TO 1500', SPOTTED 35 SKS CMT. PULLED CASING TO 900', SPOTTED 35 SKS OF CMT. PULLED CASING TO 270', AND CIRCULATED CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4412	4427		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: UNITED OIL WELL CMTG #2378 60/40 POZ 4% GEL

DATE 10-27-08
INV. NO. 2009060620

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

[Handwritten initials]