

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20611-00-00
Spot: SESENW Sec/Twnshp/Rge: 22-31S-9W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MUIR C Well #: 1
County: HARPER Total Vertical Depth: 4535 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4534		220 SXS CMT
SURF	8.625	326		250 SXS CMT

147.39

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2008 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4380' AND CAP WITH 4 SKS OF CMT. RECOVER CASING. SPOT 35 SKS AT 1500', 35 SKS AT 900' CIRC CMT FROM 370-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/22/2008 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4380', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM AND PULLED TO 1500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 370', WHERE CMT WAS CIRC. TO SURFACE. WELL PRESSURED UP OVER NITE. AND BLEW PART OF TOP PLUG OUT OF HOLE. TIED ONTO WELL AND SQUEEZED 15 SKS OF CMT DOWN CASING. WILL CHECK AGAIN IN 24 HOURS TO MAKE SURE WELL IS PLUGGED.

Perfs:

Top	Bot	Thru	Comments
4440	4450		

INVOICED

DATE 10-27-08
INV. NO. 2009060623


RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CMTG #2226 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

