

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20280-00-01 *KCC cep 10-22-08*  
Spot: SW 1/4 Sec 17-Twship/Rge: 17-17S-3W  
*690* feet from S Section Line, *3180* feet from E Section Line  
Lease Name: DALE REESE Well #: 1  
County: MCPHERSON Total Vertical Depth: 3700 feet

Operator License No.: 6306  
Op Name: TOM BROWN CONSTRUCTION, INC.  
Address: 24506 BONNET RD  
ASTOR, FL 32102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3540		3072 SX
SURF	8.625	320		320 SX

*120.25*

Well Type: SWD UIC Docket No: D19147.0 Date/Time to Plug: 06/18/2008 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 4 SXS CEMENT. CIRCULATE WITH CEMENT FROM 350' TO SURFACE.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/19/2008 3:30 PM KCC Agent: GREG EVES

Actual Plugging Report:  
CUT 2" FIBERGLASS TUBING OFF AT 2500'. SET CIBP @ 2500'. CAPPED WITH 4 SXS CEMENT. PERFORATED PIPE 370'. RUN TUBING TO 370' AND PUMPED 160 SXS CEMENT TO CIRCULATE TO SURFACE.

Perfs:  
**INVOICED**  
DATE 7-15-08  
INV. NO. 2009060095

RECEIVED  
KANSAS CORPORATION COMMISSION  
**JUN 27 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENTING TICKET #35515. TOTAL = 160 SXS 60/40 POZ 4% GEL  
Plugged through: TBG

District: 02 Signed Greg Eves (TECHNICIAN)

*Pro*