

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22723-00-00

Spot: SESESW

Sec/Twnshp/Rge: 36-13S-15W

330 feet from S Section Line,

2970 feet from E Section Line

Lease Name: DILLNER SOUTH

Well #: 2

County: RUSSELL

Total Vertical Depth: 3320 feet

Operator License No.: 6296
Op Name: HOLT, IVAN LEROY
Address: PO BOX 401
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3311	0	w/200 sxs cmt
SURF	8.625	443	0	w/210 sxs cmt

107.90

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/05/2008 2:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: TOM

Company: HOLT, IVAN LEROY

Phone: (785) 483-2822

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/05/2008 4:00 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Well had casing leaks from 420' - 1100'.
Retrievable plug lost in hole at 2570' - slip fell into hole on top of plug.
Ran tubing to 2550' - pumped 7 sxs gel, followed with 50 sxs 60/40 pozmix - 4% gel cement with 200# hulls.
Pulled to 1450' - pumped 100 sxs cement with 200# hulls.
Pulled to 700' - circulated with 100 sxs cement.
Pumped 50 sxs cement down backside. Cement circulated up inside.

INVOICED
DATE 7-1-08
INV. NO. 2009060002

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 11 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

Signed

Case Morris

(TECHNICIAN)


[Handwritten signature]

PROSPECT OIL & GAS COMPANY
P.O. BOX 837 #2 DILLNER SOUTH 36-13-15W
RUSSELL, KS. 67665 SE SE SW

CONTR REVLIN DRILLING CTY RUSSELL

GEOL BRAD HUTCHISON FIELD GORHAM

ELV 1885 KB SPD 1/8/86 CARD ISSUED 3/13/86 IP P 75 BOPD & TR WTR
1880 GL DRLG COMP 1/13/86 ARB OH 3316-3320



SMP	Tops	Depth/Datum	API 15-167-22,723
*ANH	920+	965	8 5/8 " 443 / 210SX, 5 1/2 " 3311 / 200SX
GR HAVEN	2444-	559	DST (1) 2946-2970 (TOP) / 45-45-45-45, 60' GIP, REC 60' MW,
DOVER	2470-	585	W / SO ON TOP OF TOOL, SIP 452-363#, FP 33-33 / 44-44#, HP
LANG	2478-	593	1582-1571#
2ND TARK SD	2485-	600	MICT - CO, (ARB OH), SO, NAT, SET 2 7/8 " TBG AT 3316',
TARK LM	2516-	631	POP, P 75 BOPD, TR WTR, 2/12/85
TOP	2771-	886	
HEEB	3000-	1115	
TOR	3019-	1134	
LANS	3052-	1167	
ARB	3309-	1424	
RTD	3320-	1435	
*DRILLERS TOP			

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS