

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-~~2647~~-00-00 ²⁶⁶⁶⁵⁻⁰⁰⁻⁰⁰ ¹⁰⁻¹⁶⁻⁰⁸
Spot: NESWSE Sec/Twnshp/Rge: 22-27S-21E ^{apb}
978 feet from S Section Line, 1687 feet from E Section Line
Lease Name: INMAN Well #: C4-22
County: NEOSHO Total Vertical Depth: 850 feet

Operator License No.: 33503
Op Name: PAXTON GRANT, LLC
Address: 132 N OTSEGO AVE
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	850	0	
SURF	8.625	21	0	

35

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/10/2008 10:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 850' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/10/2008 11:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FRIST OF THE CEMENT TO BE PLUGGED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 PSI. 73 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
362	366	CSG	
352	354	CSG	

RECEIVED
KCC DISTRICT #3

JUL 30 2008 CPT

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 04 2008

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 8-18-08
INV. NO. 2009060254

Remarks: _____
Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PK