

4 060074

X-1 20807 KCC 45 6 R
API NUMBER 15- 193-22,507-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 22, T 9 S, R 32 W
990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4197

Lease Name Inger Well # 1

Operator: Dunne Oil Co.

County Thomas 152.78

Name & Address: 100 S. Main #410

Well Total Depth 4701 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXXXX

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Co. License Number 5104

Address Great Bend, KS

Company to plug at: Hour: 9:00PM Day: 1 Month: April Year: 1990

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling (phone) 316-792-5633

were: Order 190 sxs. 60/40 pos 6% gel 1/2# floccul per sx.

Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXXXXXXXX

Operations Completed: Hour: 9:00PM Day: 1 Month: April Year: 1990

ACTUAL PLUGGING REPORT
1st plug at 2660' with 25 sxs. Anhydrite 2648-2676'
2nd plug at 1820' with 100 sxs. Dakota 1521-1821'
3rd plug at 315' with 40 sxs. Surface pipe to 266'
4th plug at 40' with 10 sxs. wiper plug at 40'
rathole with 15 sxs.

Remarks: B-J Services Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 13 1990

INV. NO. 27842

APR 10 1990
04-10-1990
CONSERVATION DIVISION
Wichita, Kansas
Sub S

Signed 
(TECHNICIAN)

Herb Deines