

KANSAS

sp
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

12-09-1970
RECEIVED
STATE CORPORATION COMMISSION
DEC 9 - 1970
CONSERVATION DIVISION
Wichita, Kansas

15-065-20395-00-00

Operator's Full Name Don E. Pratt,

Complete Address Box #370, Hays, Kansas.

Lease Name Sproul Well No. #G-1

Location SW-NW-SE Sec. 3 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3906'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 7:15 PM Day 1 Month 12 Year 1970

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 975'/.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 12/9/70

INV. NO. 3026-W