

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 - 1971
CONSERVATION DIVISION
Wichita, Kansas
07-08-1971

15-065-20465-00-00

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Thompson Well No. 1

Location SW-SE-NE Sec. 3 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3840'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 3:30 PM Day 5 Month 7 Year 71

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Dehler
Well Plugging Supervisor

DATE 7-9-71
INV. NO. 3965-W