

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20198-00-00

02-17-1969

Operator's Full Name Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name D. Richmeier Well No. 2

Location CN/2-SW/4 Sec. 7 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3944'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 9:00PM Day 8 Month 2 Year 1969

The Above well was plugged as follows:

157'--8 5/8" Surface casing, cement circulated with 130 Sx.
Top of Dakota section @ 935'.

Circulated hole with heavy mud. Pulled DP to 1190' and displaced 100 Sx. cement thru
DP from 1190' to 865'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from
185' to 125'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/17/69
INV. NO. 9341-W

Signed: W. L. Nichols
Well Plugging Supervisor