

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1962
06-12-1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-065-03133-00-00

File No. _____ County: Graham

Location: CNE NE Sec. 8 Twp. 10 Rge. _____ (E) _____ (W) 24

Name of Field: _____ Total Depth: 4062

I have this date completed supervision of plugging of:
Lease Name: Dreiling Well No. B-1

Operator's Full Name: Imperial Oil of Kansas Inc .

Complete Address: 780 4th Natl Bk Bldg Wichita, Kansas

Plugging Contractor Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?
Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6:30PM Day 8 Month 6 Year 62

The above well was plugged as follows:

8 5/8" 219' circulated with cement - 4 1/2" 4062' with 75 sax cement.

PB 4031' - perforated 3997' - packer set at 3970' - sand broke in and

sanded packer in hole - pulled 1695' 4 1/2" to 550', circulated hole with

heavy gel through 4 1/2" at 550' (18 sax Gel), displaced 20 sax cement

through 4 1/2" at 550', heavy mud to 180', set 20 sax cement at 180', heavy

mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 6/13/62
INV. NO. 5168-W