

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 1974  
03-07-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20500-00-00

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name C. Dreiling Well No. 2

Location NE-NE-NW Sec. 8 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4085' 4080'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 9:45 PM Day 2 Month 3 Year 1974

The above well was plugged as follows:

199'--8 5/8" Surface casing, cement circulated with 165 Sx.  
4072'--4 1/2" Production casing cemented on bottom with 200 Sx. No plug-back indicated.  
Top perforations from 3996' to 4002'.

Push plug to 3900', sand well back from 3900' to 3850' and set 4 Sx. cement with  
dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and  
12 sacks gel and followed with 110 Cu. Ft. cement from 1150' to 825' then 15 sacks  
gel from 825' to 225' and followed with 30 Cu. Ft. cement from 225' to 150' then  
3 sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of  
cellar. Maximum pump-in pressure--150#. Final shut-in pressure--50#. (Mudding  
and cementing operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 3/12/74

INV. NO. 8733-W