

KANSAS

20

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas
08-31-1970

15-179-20150-00-00

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Tilton Well No. 1

Location CNE-SW Sec. 30 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4370'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Incorporated.

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 11:45 AM Day 26 Month 8 Year 1970

The above well was plugged as follows:

177'--8 5/8" Surface casing, cement circulated.
4039'--4 1/2" Production casing cemented on bottom with 200 Sx. (Top of cement by Temperature Survey @ 3460'.) Top perforations from 3811' to 3814'. No record of plug back.

Ran measuring line to bottom, found bottom @ 4005'. Sanded well back to 3775' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 100 Sx. cement from 1225' to 900' then 17 sacks gel from 900' to 200' and followed with 25 Sx. cement from 200' to 125' then 3 sacks gel from 125' to 20' and finally 10 Sx. cement from 20' to bottom of cellar. Maximum pump-in pressure-150#. FSIP-50#. (Recovered 1140' 4 1/2" Casing).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9/1/70

INV. NO. 2456-W