

KANSAS

STATE CORPORATION COMMISSION
RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1969

CONSERVATION DIVISION AGENT'S REPORT
CONSERVATION DIVISION
Wichita, Kansas

07-18-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20220-00-00

Operator's Full Name Dreiling & Hiko Bell Mining and Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Miller Well No. 1

Location SE-NW Sec. 30 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling and Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 13 Month 7 Year 1969

The above well was plugged as follows:

188'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 140' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/18/69

INV. NO. 113-W

Signed: M. L. Nichols
Well Plugging Supervisor