

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1970
CONSERVATION DIVISION
Wichita, Kansas
02-12-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20243-00-00

Operator's Full Name Dreiling and Hiko Bell Mining & Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Tilton Well No. 3

Location CNW-SW Sec. 30 Twp. 10 Rge. (E) (W)26

County Sheridan Total Depth 4013'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 4:45 PM Day 9 Month 2 Year 1970

The above well was plugged as follows:

224'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota Section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru DP
from 1200' to 875'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from 275' to
140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/12/70
INV. NO. 1414-U