

15-065-03137-00-00

Form CP-3
Rev. 6-26-62

HO
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Texaco, Incorporated,

Complete Address: Box # 60, Hays, Kansas.

Lease Name, W. G. Culp Well No. 1

Location CN $\frac{1}{2}$ -NE-NE Sec. 21 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4022

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling Company,

Address: 204 E. 6th St., Ellinwood, Kans. License No. 396

Operation Completed: Hour 11:30AM Day 25 Month 9 Year 1964

The Above well was plugged as follows:

325'--8 5/8" Surface pipe, cement circulated with 325 Sx.
4021'--4 $\frac{1}{2}$ " Production casing cemented with 125 Sx. with 135 Bbls. oil & 135 Sx. gel pumped ahead of cement. Well plugged back to 4008' with top perforations @ 3801.

Sanded well back to 3790' and set 5 Sx. cement with dump bailer. Pulled 4 $\frac{1}{2}$ " to 660' and circulated heavy gel mud (used 30 Sx. gel). Pulled 4 $\frac{1}{2}$ " to 600' and displaced 20 Sx. cement thru 4 $\frac{1}{2}$ ". Pulled 4 $\frac{1}{2}$ " to 320' and displaced 20 Sx. cement thru 4 $\frac{1}{2}$ ". Pulled 4 $\frac{1}{2}$ ", set bridge @ 30' and 10 Sx. cement to bottom of cellar. (Recovered 3400' 4 $\frac{1}{2}$ " casing)

(Mudding and cementing operations performed by Halliburton Co)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*
Well Plugging Supervisor

DATE 9/30/64
INV. NO. 9903-w