

15-055-20360-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Martin Explorations,

Complete Address 527 Union Center Building, Wichita, Kansas.

Lease Name Billings Well-No. 1

Location 155' NE of SW-SW-NW Sec. 23 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4015'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Aspen Drilling Company,

Address Box #783, Great Bend, Kansas. License No.

Operation Completed: Hour 3:45 AM Day 24 Month 8 Year 1970

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Nichols
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1970

INVOICED
DATE 8/26/70 CONSERVATION DIVISION
INV. NO. 2436-w Wichita, Kansas