

15-065-20968-00-00

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name DON E PRATT

Complete Address 1011 FORT HAYS, KANS. 67601

Lease Name MC CALL Well No. # 1-28

Location C-SE Sec 28 Twp. 10 Rge. 24 (East)(West)

County GRAHAM Total Depth 4010 FT

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HELSO CASING PULLING

Address BOX 176 - CHASE, KANS. 67524 License No. \_\_\_\_\_

Operation Completed: Hour: 2:15 PM Day: 28 Month: DEC Year: 19 81

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 172 FT<sup>ST</sup> SUR. CASING / 140 CNT<sup>ST</sup> → 5 1/2" SET @ 4009 FT<sup>ST</sup> / 200 CNT<sup>ST</sup>.  
NO PULL BACK. → PERFS. OPEN HOLE 1 FT<sup>ST</sup>  
SAND BOTTOM (HELSO) TO 3530 FT<sup>ST</sup> → 5" CNT<sup>ST</sup> → SHOT (2) REC-1710 FT<sup>ST</sup>  
ORDER - 140 ST 50/50 Pozmix 4% GEL - 3% CH-CL. → 25 ST GEL.  
5<sup>ST</sup> HULLS → 9 8 5/8" PLUG. → PUMP IN 8 5/8" WITH PUMP TRUCK.  
PUT IN → 4<sup>ST</sup> HULLS → 15 ST GEL. → 1<sup>ST</sup> HULLS → 70<sup>ST</sup> CNT.  
10<sup>ST</sup> GEL → RELEASED PLUG. AND 70<sup>ST</sup> RECEIVED  
MAX. PRESSURE - 300 LBS PSI

Amount of Surface Casing: 172 FT<sup>ST</sup> CASING / 140 CNT<sup>ST</sup>.

STATE CORPORATION COMMISSION  
CEMENTED BY FILLED CNT.  
DEC 31 1981  
12-31-81

I hereby certify that the above plugging instructions given as herein stated.

DATE 1-20-82  
INV. NO. 9029-W

Signed: Marion Schmidt  
Conservation Division Agent  
9. Dennis Hamel