

15-065-21124-00.00

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-065-21124

RECEIVED  
STATE CORPORATION COMMISSION

DEC 31 1981  
12-31-81

CONSERVATION DIVISION  
Wichita, Kansas

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name DON E PRATT

Complete Address 1011 FORT, HAYS, KANSAS 67601

Lease Name MO CALL Well No. #2-28

Location SW-SW-SW Sec. 28 Twp. 10 Rge. 24 (East)(West)

County GRAHAM Total Depth 3739 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING

Address Box 176 CHASE, KANSAS 67524 License No. 683

Operation Completed: Hour: 12:30 PM Day: 28 <sup>th</sup> Month: DEC Year: 19 81

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 128 <sup>FE</sup> SP. CUL <sup>in</sup> / 90 <sup>ST</sup> CNT. → 4 1/2" SET @ 3998 <sup>FE</sup> <sup>in</sup> / 175 <sup>ST</sup> CNT.  
PLUG. BACK T.D. 3963 <sup>FE</sup> → PERF'S TOP. 3739 <sup>FE</sup>  
KELSO - PUSHED PLUG. TO 3700 <sup>FE</sup> → PUT. 50 <sup>FE</sup> SAND + 4 <sup>ST</sup> CNT.  
SHOT (1) RECOVERED 3041 <sup>FE</sup>  
ORDERED - 140 <sup>ST</sup> 50% POZ MIX 4% GEL. 3% CA-CL. → 25 <sup>ST</sup> GEL.  
5 <sup>ST</sup> HULL'S → 8 5/8" PLUG. → PUMPED IN 8 5/8" WITH PUMP TRUCK.  
PUT IN → 4 <sup>ST</sup> HULL'S → 15 <sup>ST</sup> GEL → 1 <sup>ST</sup> HULL'S → 70 <sup>ST</sup> CNT. → 10 <sup>ST</sup> GEL.  
RELEASED PLUG. AND 70 <sup>ST</sup> CNT. (MAX PRESSURE 300 <sup>LB</sup> PST)  
Amount of Surface Casing: 128 <sup>FE</sup> CUL <sup>in</sup> / 90 <sup>ST</sup> CNT. (BY ALLIED CNT)

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED  
DATE 1-20-82  
INV. NO. 9002-W

Signed: William Schmidt  
Conservation Division Agent  
7. Dennis Hamel