

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt,
Complete Address Drawer #370, Hays, Kansas.
Lease Name McCall Well No. 1
Location SE-SE-NW Sec. 28 Twp. 10 Rge. (E) (W)24
County Graham Total Depth 4010'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address Box #405, Chase, Kansas. License No. 624
Operation Completed: Hour 1:00 PM Day 28 Month 10 Year 1971

The above well was plugged as follows:

156'--8 5/8" Surface casing, cement circulated with 150 Sx.
4006'--4 1/2" Production casing cemented on bottom with 150 Sx. Top of cement @ 3700'
(Temp. Survey). Top perforation @ 3900'.
Pushed plug to 3850', sanded well back to 3825' and set 3 Sx. cement with dump bailer.
Pulled 5 1/2" casing (2550') and squeezed well initially with 5 sacks hulls and 10 sacks
gel and followed with 100 Sx. cement from 1085' to 760' then 15 sacks gel from 760'
to 160' and finally 50 Sx. cement from 160' to bottom of cellar. Maximum pump-in
pressure-300#. Final shut-in pressure-150#. (Mudding and cementing by Allied Cement-
ing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/2/71
INV. NO. 4565-W