

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION NE NE SW
SEC. 34 TWP. 10 RGE. 24

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Brungardt
Operator Murfin Drilling Co. ~~Williamson~~ Address 617 W. Center
Wichita, Kans
Field _____ County Graham
Total Depth 4456 Feet.
Plugging Contractor same

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 233' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 700', displaced 20 sax cement through drill pipe, heavy mud to 220', set cementing plug, and displaced 15 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

[Signature]
District Conservation Agent

Date 10-15-57

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1957
CONSERVATION DIVISION
10-21-57

PLUGGING
FILE SEC. 34 T. 10 R. 24
BOOK PAGE 55 LINE 30