

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Herman Well No. G-1

Location CSE-SW Sec. 1 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 3100

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address Route #2, Great Bend, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 31 Month 3 Year 1968

The above well was plugged as follows:

245'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru

DP from 1400' to 1075'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from

240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/2/68
INV. NO. 7513-U

Signed: A. L. D. [Signature]
Well Plugging Supervisor