

15-065-20540-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,
Complete Address 905 Century Plaza, Wichita, Kansas.
Lease Name Kuhn Well No. 1
Location SW-SW-NW Sec. 3 Twp. 10 Rge. (E) (W) 25
County Graham Total Depth 4030'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 5:15 PM Day 8 Month 4 Year 1972

The above well was plugged as follows:

229'--8 5/8" Surface casing, cement circulated with 160' Sx.
Top of Dakota section 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement
thru DP from 1175' to 850'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. G. Nichols
Well Plugging Supervisor

DATE 4/13/72
INV. NO. 5544-10