

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

OCT 15 2008

CONSERVATION DIVISION
WICHITA, KS

API # 15-173-19072-0-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date 9/4/1987

Well Operator: Oneok dba Kansas Gas Service (KGS) KCC License #: 6035
(Owner / Company Name) (Operator's)

Address: Post Office Box 208 City: Wichita

State: Kansas Zip Code: 67201 Contact Phone: (316) 832 - 3184

Lease: Rectifier Well #: 598 Sec. 9 Twp. 27 S. R. 1 East West

SE E E E E NE E E E E SE E E E E Spot Location / QQQQ County: Sedgwick

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

114 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10 inches Set at: 127 feet Cemented with: unknown Sacks

Production Casing Size: N/A Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: N/A

Elevation: 1315 (G.L. / K.B.) T.D.: 210' PBTD: _____ Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Remove coke backfill and anode wires from bore hole. Pump grout through tremie pipe and from TD (300') to 3 feet below surface. Backfill and grade soil to original condition.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Log not available

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dale Hayse, Hayse Management Services

Consultant for Oneok, DBA KGS Phone: (620) 548 - 2369

Address: PO Box 107 City / State: Mullinville, KS

Plugging Contractor: Hayse Management Services KCC License #: 639
(Company Name) (Contractor's)

Address: PO Box 107 Mullinville, KS 67109 Phone: (620) 548 - 2369

Proposed Date and Hour of Plugging (if known?): 10-27-08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent \$3500

Date: 10-13-08 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 2
AA

DEEPWELL GROUND BED DATA

Date:

Job No. Station No. #: 903 Facility/Line: 15th Street
 Client: Kansas Gas Services Drilling Contractor: McLean's C P Installation, Inc.
 Subject: Deep Well
 Depth: 210' Dia. 9" Casing: 80' State: Kansas County: Sedgwick
 Type of Backfill: SWS
 Anodes Description: (1) set of (10) Anotec 2684 anodes

Remarks:

Depth:		Electrical Log		Anode Log		
		Volt		Anode #	Depth	Volt
0'-10'	Dirt	3.5	80'			
10'-45'	Sand and Gravel	3.0	90'			
45'-210'	Blue Clay w/Thin	2.8	100'			
	Layers of Limestone	2.9	110'			
		2.0	120'			
		2.1	130'			
		1.4	140'			
		4.2	150'			
		3.2	160'			
		1.1	170'			
		4.0	180'			
		4.7	190'			
		4.5	200'			
		2.4	210'			

RECEIVED
 KANSAS CORPORATION COMMISSION

OCT 15 2008

CONSERVATION DIVISION
 WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ONEOK, INC. DBA KANSAS GAS SERVICE
7421 W 129TH ST
OVERLAND PARK, KS 66213-2634

October 21, 2008

Re: RECTIFIER #598
API 15-173-19072-00-00
9-27S-1E, 1320 FNL 114 FEL
SEDGWICK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 19, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000