

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-159-22522-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 1-17-07

Well Operator: Hupfer Operating, Inc. KCC License #: 30380
(Owner / Company Name) (Operator's)

Address: P.O. Box 216 City: Hays

State: KS Zip Code: 67601 Contact Phone: (785) 628-8666

Lease: Bayer Well #: 2 Sec. 31 Twp. 19 S. R. 10 East West

NW - NE - SW - SE Spot Location / QQQQ County: Rice

1170 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1800 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 266 Cemented with: 225 Sacks

Production Casing Size: 5 1/2" Set at: 3305 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Arbuckle open hole 3305 to 3313, Lansing 3198 to 3204, & 3047 to 3050.

Elevation: 1802 (G.L. / K.B.) T.D.: 3313 P.B.T.D.: _____ Anhydrite Depth: 482
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand off bottom w/ 5 sxs. cement on top. Set bridge plug @ 2900' w/ 2 sxs. cement on top, 35 sxs. cement @ 1300', 35 sxs. cement & 200# hulls @ 800', 90 sxs. cement @ 290' to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mike Kelso/Dennis D. Hupfer
(785) 628-8666 Phone: (620) 938-2943

Address: P.O. Box 467, Chase City / State: Chase, KS 67524

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529
(Company Name) (Contractor's)

Address: P.O. Box 467, Chase, KS 67524 Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): ± Nov. 3, 08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-17-08 Authorized Operator / Agent: Dennis D. Hupfer
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 20 2008

CONSERVATION DIVISION
WICHITA, KS

Dist 2
PH



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HUPFER OPERATING, INC.
PO BOX 216
HAYS, KS 67601-0216

October 24, 2008

Re: BAYER #2
API 15-159-22522-00-00
31-19S-10W, 1170 FSL 1800 FEL
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 22, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000