

4674 FEL
1942 FSL

Make Bill out Do Not Send.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Amended copy

Form CP-1
September 2003

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

API # 15-167-22144-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7/11/1983

Well Operator: JASON OIL COMPANY KCC License #: 6622 33813 (Operator's)

Address: P.O. BOX 701 City: RUSSELL

State: KANSAS Zip Code: 67665 Contact Phone: (785) 483-8027

Lease: GROSS A Well #: 1 Sec. 5 Twp. 15 S. R. 13 East West

SW - NE - NW - NE Spot Location / QQQQ County: RUSSELL

560 4674 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1930 1942 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 684 Cemented with: _____ Sacks

Production Casing Size: 5 1/2 Set at: 3167 Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFS AT 2912-2916, 3084-3087, BRIDGE PLUG 2960 LINER 3000-3250
Sand at 2575 5SKS cement. pipe recovery 1600

Elevation: 1727 (G.L. / K.B.) T.D.: 3175 PBDT: _____ Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): HAYS DISTRICT REGULATIONS
1250 125SKS 300# Halls. 700 170SKS 200# Halls.
Top off 2.5SKS. 320SKS 500# Halls

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? N/A

RECEIVED
KANSAS CORPORATION COMMISSION

OCT-20-2008

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission, WICHITA, KS

List Name of Company Representative authorized to be in charge of plugging operations: RICHARD MCINTYRE

Phone: (620) 727-3410

Address: 190th US 56 HWY City / State: ELLINWOOD KANSAS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925 (Contractor's)

Address: 190th US 56 HWY Phone: (620) 727-3410

Proposed Date and Hour of Plugging (if known?): APR-JUN 2008 6-23-08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4-9-08 Authorized Operator / Agent: _____ (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*well plugged-KCC-AKT

Dist 4
PKT

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
7/2/2008	987

Bill To
Jason Oil Box 701 Russell, KS 67665

P.O. No.	Terms	Lease Name
	net	Gross A 1

Description	Qty	Rate	Amount
Rig Time	17.5	185.00	3,237.50T
Floor Rental		125.00	125.00T
Shots	3	200.00	600.00T
Torch		50.00	50.00T
Bored Collar		40.00	40.00T
Welding		100.00	100.00T
Water Truck	3	75.00	225.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
Fresh Water		20.00	20.00T
Subtotal			4,452.50
7% Fuel Surcharge		7.00%	311.68T
6-19-08 Drove to location, raised pole, checked hole, hit bridge at 575', ran bailer, knocked out bridge, tagged tubing at 2575', dug cellar, unpacked casing head, set floor, pulled slips, had 16" stretch, ripped casing at 2010', worked pipe, pulled slip collar off casing, welded new collar on casing, ripped casing at 1840', worked pipe, ripped casing at 1600', pipe came free, pulled casing up to 1250', swedge in, drove home.			
6-23-08 Drove to location, pumped 125 sacks, 300# hulls at 1250', pulled casing up to 700', pumped 170 sacks, 200# hulls to surface, pulled casing out, topped off with 25 sacks, tore down floor and rig.			
Subtotal			\$4,764.18
Sales Tax (7.3%)			\$347.79
Total			\$5,111.97

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 20 2008
CONSERVATION DIVISION
WICHITA, KS