

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: EOG Resources, Inc.
Address: 3817 NW EXPRESSWAY, SUITE 500 OKla City, OK 73112
Phone: (405) 246-3100 Operator License #: 5178 PERKCC
Type of Well: D&A D/H KCC PRT PER CP-2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/10/2008 (Date)
by: Lynn Reimer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No

API Number: 15-081-21701-0000 ⁰¹ KCC PRT
Lease Name: APSLEY 1
Well Number: # 2
Spot Location (QQQQ): _____ - SE - NE - NW
1072 Feet from North / South Section Line
2031 Feet from East / West Section Line
Sec. 1 Twp. 28 S. R. 34 East West
County: HASKELL
Date Well Completed: 3/31/2007 ^{original dt.}
Plugging Commenced: 9/11/2008
Plugging Completed: 9/15/2008

Producing Formation(s): List All (if needed attach another sheet)
LOWER MORROW Depth to Top: 5293' Bottom: 5362' T.D. 5800'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LOWER MORROW	DRY	Surface	1699'	8 5/8"	1699'	None
		Surface	5730'	4 1/2"	5730'	1807'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

POH w/ tbg . Load casing w/mud & set 4 1/2" 10K CIBP @ 5243' , cap w/ 2 sks cement . Cut & pull 4 1/2" casing from 1807' . Run tbg @ 1807' mix & spot 110 sks class "C" cement up to 1400' , POH w/ tbg & WOC . Tag TOC @ 1552' . Pull up hole w/tbg @ 750'
Mix & spot 50 sks class "C" cement up to 570' , POH w/ tbg & top out 34' - 4' w/ 10 sks cement . Dig out & cut off 8 5/8" csg 4' below ground level
weld ID plate .

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338 **RECEIVED**
Address: P. O. Box 1706 Duncan, OK 73534 **KANSAS CORPORATION COMMISSION**
Name of Party Responsible for Plugging Fees: EOG **OCT 01 2008**
State of OK County, OK, ss. **CONSERVATION DIVISION**
Bev Christensen **WICHITA, KS**

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Bev Christensen
(Address) 3817 NW Exp Ste 500 Oklahoma City OK 73112-1483

SUBSCRIBED and SWORN TO before me this 26th day of September 2008
Kaye Dawn Rockel My Commission Expires _____ Notary Public
Notary Public
State of Oklahoma
Commission # 04009575 Expires 10/21/08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202