


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 28 Twp. 28 Rge. 2 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Rex and Morris
Lease Name Shorey Well No. 1
Office Address Box 334 Eldorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 5-20-56 19
Application for plugging filed 5-20-56 19
Application for plugging approved 5-20-56 19
Plugging commenced 5-20-56 19
Plugging completed 5-20-56 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation Arbuckle Depth to top _____ Bottom 3447 Total Depth of Well 3447 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water	0	107	8 5/8	107	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3447-107 Fill W/heavy mud
107 Set good permanent plug then 1/2 sax hulls then 15 sax cement thru drill pipe
20' Set good permanent plug then 1/2 sax hulls then 10 sax cement to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1956
5-25-56
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) James M. Armour James M. Armour
817 Central Building Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of May, 19 56

My commission expires December 29, 1959

Marjorie Hall
Marjorie Hall Notary Public.

PLUGGING
FILE SEC 28 T 28 R 2E
BOOK PAGE 64 LINE 38



DRILLING LOG

COMPANY: Rex & Morris
 CONTRACTOR: Shaver-Armour, Inc.

Location: RR 38 E
 28-28-2E
 Sedgwick

WELL NAME: Shorey # 1

Elevation: 1331 Ground

DATE STARTED: May 13, 1956
 COMPLETION: May 20, 1956

CORRECTION
 102' 8 3/8"

FORMATION	TO		
Swinson	4		
Sandy Clay	15		
Blue Clay & Lina breaks	76		
shale & Anhydrite	95		
Blue shale & Lina	107		
Anhydrite w/shale & shell	105		
anhydrite	200		
Lina & Shale	240		
Lina w/shale Strata	1790		
Shale & Lina	1890		
Lina Strata & shale	2170	Essex City	2140
Sandy shale	2196	Cherokee shale	2308
Lina w/shale Strata	2390	Hindertown	3326
Shale	2516	Waseon	3379
Shale & Lina	2605		
Lina	2726		
Lina & Shale	2840		
Lina w/shale Strata	2885		
Sandy shale & Lina	2945		
Shale	3073		
Lina	3093		
Lina & Shale	3126		
Shale	3379		
Lina & Shale	3420		
Shale	3432		
Lina	3447		

(NAME OF WELLS) as
 (WELLER COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

JAMES ARMOUR, INC.
 J. James Armour
 James Armour, Sec. Treas.

Subscribed and sworn to before me this 24th day of May, 1956.
Marjorie Hall
 Marjorie Hall, Notary Public

My commission expires December 15, 1959.

RECORDED
 STATE LAND OFFICE
 MAY 24 1956

PLUGGING
 FILE SEC. 28 T. 29 R. 2E
 BOOK PAGE 64 LINE 38